

Exhibit E

U.S. Bank Stadium is an active venue hosting a variety of events during the course of this Project's construction schedule. Event logistics and event programs take precedence over construction activities. Close coordination with construction activities that create noise and limit access to spaces will be paramount.

Non-Work Days:

- July 30 – Guns N Roses Concert
- August 12 – Cold Play Concert
- August 18 – Justin Bieber Concert
- August 27 – Vikings vs 49ers
- August 31 – Vikings vs Dolphins
- September 8 – U2 Concert
- September 11 – Vikings vs Saints

Project includes the design, coordination, installation, start-up and testing of the following items:

Description of Electrical Requirements to be provided:

Project work to be complete by August 25, 2017.

- Invert Cord Drops Invert Receptacle 180* on Food Service Cord Drops
- Curds & Cakes Add (2) Fryer Receptacles Furnished by Others
- Buffalo Wild Wings Provide Cords and Plugs to Split Action Station
- FMP Club Provide Cords and Plugs to Split Action Station
- Truss Bar (1) Dedicated 20A GFI Receptacles for Food Warmer
- Stand 118 Add (1) 50A 208V Single Phase Circuit and 6-50R Receptacle for Convection Oven
- Delta 360 Club 30A 120/208V 1 Phase Receptacle for Action Station
- FMP Club Action Stations & Bev Coolers (2) 60A Services for Action Stations, (8) Dedicated Cooler Receptacles
- BW3 Club Action Stations & Bev Coolers (2) 60A Services for Action Stations, (8) Dedicated Cooler Receptacles
- FMP Club Beverage Coolers (2) 20A Dedicated Cooler Receptacles NE Corner of Club
- Install necessary power inside the Delta Club to allow for relocation of two existing food portables.
- Add a drop cord in FMP to power 4 single visi coolers, one freezer, and two registers.

Project work to be complete by September 7, 2017.

- Concourse (1) Pedestal, (2) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (2) Dedicated 20A GFI Receptacles
- Concourse (4) Pedestals, (8) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (2) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (1) 30A 3 Phase TL, (2) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (1) 30A 3 Phase TL, (2) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (2) Dedicated 20A GFI Receptacles
- Concourse (4) Pedestals, (8) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (2) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (1) 30A 3 Phase TL, (2) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (1) 30A 3 Phase TL, (2) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (2) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (2) Dedicated 20A GFI Receptacles
- Concourse (2) Dedicated 20A GFI Receptacles Added to Existing Pedestal
- Concourse (1) Pedestal, (2) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (2) Dedicated 20A GFI Receptacles
- Concourse (1) Pedestal, (1) 30A 3 Phase TL, (2) Dedicated 20A GFI Receptacles
- Club TV Signage
 - Requirements include the following:
 - To include running of all electrical wiring, cabling, and data required for televisions in each location.
 - Installing of all television mounts and physical mounting of televisions to the television mount
 - Testing of all televisions upon completion
 - Locations include:
 - Delta – 7
 - Medtronic – 7
 - Hyundai – 2